



Mere energetske efikasnosti (EE) i smernice za njihovo sprovodenje- program obuke za građevinske kompanije i nadzorne organe

Rezultati analize javnog građevinarstva i utvrđene mere

Zlatko Bačelić Medić
z.bacelic@ic-group.org
10/11/2016

Sadržaj

- › Razmatrane EE & RE mere
- › O energetskoj reviziji
- › Utvrđene mere
- › Pregled rezultata energetske revizije

Razmatrane EE & RE mere

- › GRAĐEVINARSKE MERE
 - › Izolacija spoljašnjih zidova
 - › Krovna izolacija
 - › Podna izolacija (na prizemlju) – posebni slučajevi
 - › Zamena prozora i vrata

Razmatrane EE & RE mere

- › MAŠINSKE MERE
 - › Poboljšanje sistema grejanja
 - › Montaža TRV
 - › Zamena pumpi
 - › Zamena, popravka i čišćenje postojećih grejnih distributivnih sistema
 - › Zamena goriva – gradsko grejanje, biomasa, pumpe za grejanje
 - › Priprema sanitарне tople vode – solarni grejni sistemi

Razmatrane EE & RE mere

- › ELEKTROTEHNIČKE MERE
- › Sistem osvetljenja
 - › Poboljšanje postojećih sistema osvetljenja
 - › Zamena postojećih sistema osvetljenja
- › Ostali aparati
 - › Pumpe, električni aparati, itd. (zavisno od situacije)
 - › Uklanjanje električnih grejalica

O energetskoj reviziji...

› Energetska revizija :

...je provera, pregled i analiza tokova energije, radi očuvanje energije u objektu, proces ili sistem smanjenja dotoka energije u sistem bez negativnih posledica po izlaz (e).

Wikipedia

› Za pripremu energetske revizije, potrebne su:

- › Opšte informacije o objektu
- › Informacije o obrascima potrošnje u objektu
 - › Zauzetost/naseljenost objekta
 - › Režimi rada grejanja/hlađenja
 - › Obrasci upotrebe električnih sistema

O energetskoj reviziji...

- › Nacrt i plan objekta
 - › Građevinski/arhitektonski
 - › Mašinski
 - › Elektrotehnički
 - › Ostali (ako su od koristi)
- › Informacije o energetskoj potrošnji u objektu
 - › Nosilac potrošnje grejne energije i troškovi
 - › Potrošnja i troškovi električne energije
- › Informacije/potvrda o ugrađenim električnim aparatima u objektu
 - › HVAC
 - › SHW sistem
 - › Električni potrošači

O energetskoj reviziji ...

- › TOK RADA
 - › Priprema
 - › Prikupljanje dostupnih informacija o objektu (-ima)
 - › Nacrti, obrasci upotrebe, potrošnja, troškovi, itd.
 - › Planiranje obilaska lokacije
 - › Dogovor o obilasku lokacije
 - › Obilazak lokacije
 - › Prikupljanje informacija na licu mesta o opremljenosti objekta
 - › Prikupljanje informacija od tehničkog osoblja
 - › Potvrda/provera informacija o pripremnoj fazi
 - › Prikupljanje ostalih bitnih informacija

O energetskoj reviziji ...

- › TOK RADA
 - › Kancelarijski posao
 - › Priprema svih informacija za izveštaj
 - › ... karakteristike omota
 - › ... karakteristike HVAC sistema
 - › ... karakteristike električnih sistema
 - › Priprema za analizu potrošnje energije
 - › Priprema za analizu troškova energije
 - › Priprema modela energije u objektu
 - › Uspostavljanje referentne potrošnje
 - › Utvrđivanje mera EE
 - › Procena mogućih posledica EE mera
 - › Potrošnja energije
 - › Troškovi energije

O energetskoj reviziji...

Hegy Áudit, Rész A 077
Városi - Dózsa György utca 10.

4.00
07.2.2015

5. BUILDING STATE DESCRIPTION

The following chapter details the existing condition of the building including envelope constructions, mechanical and electrical systems, and general condition. The energy consumption data, both reported and calculated, are presented in Chapter 6.

5.1. BUILDING LOCATION

The building is located in the center of Vukovar with good access for pedestrians and vehicles. It is surrounded with other buildings with different characteristics in architecture and period of construction. According to interviews with the staff and according to the list of buildings with historical value issued by Ministry of Culture, the Dormitory for Men building doesn't have any historical value and therefore no restrictions for renovation work.



Figure 2 – Building location

5.2. GENERAL CONSTRUCTION DESCRIPTION

Audited building	Dormitory Men
Date of auditing	1.2.2014
Involved sector*	Residential
Year of construction*	1936
Type of construction*	Masonry concrete
No. of floors/levels*	4 (basement, ground floor, 2 floors)
Gross area [m ²]	5.300,2
Volume [m ³]	11.355,5
Occupants	300
Heating system*	13 obj. - 13 As.
Heating source*	

Table 2 – General description

O energetskoj reviziji ...

Hrg-Audi-Auto-B077
Vrhovo - Dobrovnik, Rep. Srpske
07.12.2013

The floor usage is similar for all other floors which are mostly residential rooms. The basement also comprises the substation, storage and training rooms.

Building Floor	Space type	Height m	Kerred areas m ²	Unshaded m ²	Total areas m ²	Kerred volume m ³
Basement	Substation, storage, training room.	2.6	290.0	260.0	550.0	550.0
Ground floor	Rooms, hallways	2.5	295.6	275.0	570.6	1,426.5
First floor	Rooms, hallways	2.5	295.6	275.0	570.6	1,426.5
Second floor	Rooms, hallways	2.5	295.6	275.0	570.6	1,426.5
TOTAL			2,922.5	2,526.0	5,448.5	

Table 3 – Usage by floor

5.2.1 Building layout

The building layouts were obtained. The building is spread along the main axis. The shape of building is simple as it only has one central corridor and rooms concentrated on both sides of the corridor.

Hrg-Audi-Auto-B077
Vrhovo - Dobrovnik, Rep. Srpske
07.12.2013






Figure 3 – Basement layout

O energetskoj reviziji...



O energetskoj reviziji ...



O energetskoj reviziji ...

Report No. 027
Vukovar - Osječko polje

Page 20
07.2.2013

5.2.2. Building Physical Characteristics

All building elements were examined during the site visit. During the examination, certain deficiencies which cause large thermal losses were found. The following tables present the characteristics of each building element including:

- year of renovation
- existing layers of the element (where applicable)
- overall element thicknesses (where applicable)
- assessment of the element condition in order to evaluate whether construction measures are necessary prior to application of energy efficiency measures
- visible damage on each building element

The most important results apart from the condition assessment, is the elaboration on building element areas, orientations and U-values of each element.

5.2.2.1. Walls

Building was constructed during 1936, structurally it consists of walls made out of full brick and concrete with a thickness of 30 cm and plaster from both sides. Outside walls are assessed to be in quite a good condition from the structural point of view with some minor damages in plaster. It is recommended to install thermal insulation on the facade but minor damages have to be treated prior to EPS installation.

The existing layers are presented in Table 5. Existing walls can be seen in photos, Figure 6.

Type	Description	Area [m ²]				Existing "U"-value	Proposed "U"-value
		h	w	s	c		
Wall type 1	Plaster, brick, plaster	2660	512.1	222.2	466.2	1.629	0.222
Total wall		2660	512.1	222.2	466.2	1.629	

Table 4 – Walls summary

Wall type 1 1492.1 m ²			
Building			
Layer name	d	λ	R
[mm]	[W/mK]	[m ² K/W]	
Plaster	25	0.06	0.031
Brick	200	0.01	0.270
Plaster	25	0.06	0.031
U-value [W/m ² K]	1.629		

Table 5 – Wall U-value calculation

Removed			
Renovated			
Layer name	d	λ	R
[mm]	[W/mK]	[m ² K/W]	
Plaster	25	0.06	0.031
Brick	200	0.01	0.270
Plaster	25	0.06	0.031
CPS	100	0.04	2.500
Façade plaster	5	0.06	0.036
U-value [W/m ² K]	0.222		

Report No. 027
Vukovar - Osječko polje

Page 21
07.2.2013



Figure 6 – Walls

5.2.2.2. Windows and External Doors

In 2000, most of the old metallic frame windows were replaced with new PVC windows. New windows are double glazed with PVC frame but some minor deficiencies were noticed during inspections since some PVC windows cannot be closed properly. It is recommended to fix the closing mechanism on windows. This measure is considered to have a slight improvement in reducing the infiltration heat losses. It is also recommended to replace the remaining old windows. The table below describes the window area and U-value.

Type	Description	Area [m ²]		Existing "U"-value	Proposed "U"-value
		South	East-South		
Windows 1 - PVC frame	Double glazing	20	20.0	1.000	1.000
Windows 2 - Metal frame	Double glazing	670	0.0	4.500	1.400
Total windows				440.0	

Table 6 – Windows description

Doors were also inspected. Doors were replaced during 2000 when new aluminum frame and double glazed doors were installed. According to the visual inspection doors are assessed as good material and it is not recommended to replace them.

The table below describes door characteristics.

Type	Description	Area [m ²]		Existing "U"-value	Proposed "U"-value
		South	East-South		
Glass 1 - Alum. frame	Double glazing	0.0	25.5	1.000	1.000
Total doors					

Table 7 – Door description

O energetskoj reviziji ...

Hegyelme, Belišić 077
Vrhovo - Dobrovare, BiH

Co
07.1.2013



Figure 7 – Windows/doors

5.2.2.3. Floor

The floor is in a relatively good condition, but it has bad thermal properties. Despite that it is not recommended to insulate the floor since this measure is in general expected to have a large investment for a small benefit compared to other elements of the envelope. However if a renovation is going to take place in future then it is recommended to implement EE measures along with other refurbishment works.

The basement floor U-value and areas are presented in Table 8 and Table 9.

Basement type 2 Area = 255,2 m ²			
Layer name	a [m]	b [W/m ²]	c [m ² /W]
Brick	20	1.60	0.015
Brick	20	1.63	0.020
Wood tiles	20	0.13	0.155
Mineral insulation	10	0.16	0.005
Concrete slab	120	2.00	0.030
U-value [W/m ² K]		1.973	

Table 8 – Basement floor U-value calculation

Basement floor	Area	existing U-value	proposed U-value
Brick + wood + mineral + concrete slab	[m ²]	[W/m ²]	[W/m ²]
255,2	1.973	1.973	

Table 9 – Floor description

Hegyelme, Belišić 077
Vrhovo - Dobrovare, BiH

Co
07.1.2013

5.2.2.4. Roof

According to the visual inspection, the roof has a solid wooden structure forming a regular geometric shape. Roof is assessed to be structurally sound. However, it's covered with asbestos corrugated plates which need to be removed and handled carefully by professionals. New covering should include wooden planks, vapor barrier and metallic corrugated sheets. It is recommended to install thermal insulation on the roof with a rock wool layer to be laid on the slab and covered with a protective layer of screed, but only after construction work are completed.

The layers and U-value calculation for the existing and proposed roof are presented in Table 10 and Table 11.

Roof type 1 255,2 m ²			
Existing		Renovated	
Layer name	d [mm]	A [W/m ² K]	B [W/m ² K]
Plaster	20	0.00	0.00
Concrete slab	200	2.6	0.08
Rock-wool	120	0.04	0.00
Screed	50	1.05	0.00
U-value [W/m ² K]		0.036	

Table 10 – Roof U-value calculation

	Real	Area	existing U-value	proposed U-value
Type	Residential	[m ²]	[W/m ² K]	[W/m ² K]
Roof type 1	Rock-wool	255,2	0.036	0.036

Table 11 – Roof description



Figure 8 – Roof

5.3. SANITARY HOT WATER

A solar thermal heating system was investigated and study of a solar thermal system for SHW preparation was done in order to assess the currently installed system.

Sanitary hot water is produced in the main heating plant with a diesel boiler and is supplied to buildings according to demand. However, currently it is not functioning and SHW is prepared locally in each building.

O energetskoj reviziji ...

Report No.04, Ref ID: 027
Version - Draft version rev. *

ESD
07.2.2013

In addition to this, Dormitory for men has installed solar panel with a total of 22 panels (1.2x2 m) and 4 water storage tanks of 1000l each. The tanks are also connected to the electrical system for water preparation when solar panels are not supplying to full requirement, but currently they are turned off due to high energy expenses. SHW substation is located in the basement of the Dormitory and no major deficiencies were noted.

Sanitary hot water consumption is estimated to around 1334 m³/a, meaning 77 MWh energy (calculated with 50°C average annual cold water temperature and 60°C desired SHW temperature).

Type	Description	Quantity
Solar panels	- D = 1.2x2 m	22
Hot water tank	- V = 1.000l each	4
Expansion vessel	- V = 100 l each	2
Pumps	- V = 10 l/s 350/10	1

Table 12 – Installed equipment for Sanitary Hot water production and distribution



Figure 9 – SHW preparation

5.4. SPACE HEATING

Kosovo Academy for Public Safety campus has a centralized heating system with one heating plant serving all buildings within campus. Heating plant runs on diesel boilers. Entire heating system was refurbished during 2000-2002. The water is distributed through an underground pipeline system. Site visit revealed that the underground piping system was recently replaced (in 2014) (Dormitory men, Dormitory women, Administration, New Dormitory, and Range shooting). The old pipes were replaced with new pipes insulated with glass wool and laid into concrete trenches. The interview revealed that second phase of the project is expected to be finalized during 2015 when pipes that supply Sports Hall and School building will be replaced with new. This was already implemented in the second half of 2015 according to information that was received. Every building (besides Steve Benet building, Healthcare building and Building 14) has its own substation, where the hot water enters into the hot water headers and then through the circulating pumps to upper floors.

Report No.04, Ref ID: 027
Version - Draft version rev. *

ESD
07.2.2013




Figure 10 – Technological scheme of heating

5.4.1. Hot Water Preparation and Distribution

Substation is located in the basement covering an area of 12 m², which is sufficient for the current heating system and storages and it would allow placement of potential additional equipment.

Heating substation has been renovated in 2000 when new pump, valves and piping were installed. Heating hot water is circulated with one Wilo pump without VFD. A three way valve is installed and working properly. The distribution pipes within the substation are well insulated with some minor deficiencies caused during some construction works. However, personnel didn't report any leakages in the system.

The installed equipment for heating preparation and distribution is listed below:

Type	Description	Quantity
Pumps	- 1 x 340/7, type Wilo	1

Table 13 – Installed equipment for heating preparation and distribution



Figure 11 – Substation

O energetskoj reviziji ...

Hegy Árkó, Rész A 077
Működési-Diagramok
07.12.2013



Figure 12 – Radiators installed in the building

Radiators

Baseline

Type	Dimensions	No.	Capacity	Total
PDP	500x1000	21	2,229	47,8
PDP	500x2000	30	2,229	173,9
PDP	500x1400	20	5,126	102,3
PDP	500x1600	3	5,371	28,6
PDP	500x1800	5	4,017	20,1
PDP	500x2100	2	5,704	7,4
Total		124	52,044	519

Table 14 – Specification of radiators

Internal temperature was measured in different places and the results show 19-22°C in most of the rooms. However there was a higher fluctuation in hallways where the measured temperature range was between 12-18°C.

The calculated system power for the baseline scenario is 432 kW (see Annex 2 for calculation details) which is above the total installed radiator capacity of 336 kW, and the comfort conditions are not met due to low capacity of radiators compared to heat losses.

After introducing EE measures, heat demand will drop significantly (200 kW), which means radiators capacity will be oversized. Therefore, it is recommended to install TRVs on each radiator.

5.5. AIR CONDITIONING

There is no central cooling system in the building.

5.6. SPACE VENTILATION

There is no central ventilation system installed.

5.7. ELECTRICAL SYSTEM

There are no data regarding the internal electricity distribution network. In general, the lighting is in a poor condition in terms of EE and there are no replacement parts

Hegy Árkó, Rész A 077
Működési-Diagramok
07.12.2013

available. Fixtures are T8 linear fluorescent lamps operated by conventional control gear (CCG) which has placed under reflecting grill for soft light distribution and incandescent 100 W lights. Lighting measurements accounted for 190-200lux in most of the rooms and approximately the same in hallways. It is recommended to replace the lighting system with a more efficient one which will also ensure higher lighting levels which will meet the national standards. A lighting simulation of one characteristic room is provided on the figure below.




Figure 13 – Lighting simulation of one characteristic room

Since the baseline is calculated for the condition where all the lamps are in place and operating, the new lamps to be installed are only included in the Table of the Investment.

O energetskoj reviziji ...

Hegy Audi, Kozar x 077
Vakuum - Dometic inc.

ZGB
07/2/2013

Table below describes identified lighting fixtures and their rated power.

Lighting

Facilities

Type	No.	Bulbs	Watts	Ballast	Watts/a
13 fluorescent 20W	4	2	56	13%	531,1
13 fluorescent 12W	1	2	56	13%	327,5
13 fluorescent 20W	11	2	56	13%	903,4
headlights 100W	25	1	100	0%	2420,0
TOTAL	105		203		9,227,3

Table 15 - Lighting specification



Figure 14 - Lighting fixture

Electrical equipment is mostly PCs, TV, and technical equipment.

Equipment

Facilities

Type	No.	Watts	Watts/a
PC	10	250	3,000
TV	1	250	742
cooler	2	2,000	5,100
fu. mcs	2	330	702
laptop	6	1,300	5,310
TOTAL	4,040		15,692,0

Table 16 - Electrical equipment specification

Hegy Audi, Kozar x 077
Vakuum - Dometic inc.

ZGB
07/2/2013

ENERGY CONSUMPTION

The dormitory buildings are a part of a larger academy center campus including three dormitories, School, Administration building, logistic building, Steve Benet, Building 14, Sport hall, Healthcare building, Kitchen. According to the interview there is no energy meter (heat or electrical) for each separate building. In order to obtain an orientation figure for metered consumption of each building, the total consumption is distributed according to a ratio of total calculated consumption. The results are presented in the following section.

The results are presented in the following section.

REPORTED/MEASURED ENERGY CONSUMPTION

The results are presented in the tables below.

Building	Total measured consumption Watts/a	Calculated consumption Watts/a	% share	
			Office	Residential
076-Y10-(XPS_School)	20,7	20,7	-	0,000
077-Y10-(XPS_Dormitory_res.)	62,5	(2,8%) 321,1	-	-
078-Y10-(XPS_Dormitory_warm.)	513,9	(10,0%) 265,5	-	-
079-Y10-(XPS_Healthcare_bldg.)	74,9	(2,4%) 62,2	-	-
080-Y10-(XPS_Administrative_bldg.)	197,9	(6,2%) 194,9	-	-
081-Y10-(XPS_Kitchen_hall)	316,8	(10,2%) 482,3	-	-
082-Y10-(XPS_Leaving_Plaza+ice+cafeteria)	9,0	(0,2%) 9,7	-	-
083-Y10-(XPS_Sport_hall+Kitchen)	39,0	(1,1%) 71,7	-	-
40x.audited Y10-(XPS_Bldg_Hall)	39,2	(1,0%) 25,2	-	-
40x.audited Y10-(XPS_Cafeteria)	101,0	(2,8%) 35,9	-	-
40x.audited Y10-(XPS_Administrative_bldg.)	60,4	(2,1%) 34,3	-	-
40x.audited Y10-(XPS_Leaving_hall)	47,9	(1,3%) 39,7	-	-
40x.audited Y10-(XPS_School_hall)	5,9	(0,2%) 7,2	-	-
40x.audited Y10-(XPS_Foyer)	5,0	(0,2%) 27,5	-	-
40x.audited Y10-(XPS_kitchen)	79,3	(2,2%) 93,4	-	-
TOTAL	9,161,2	100,4 264,7		

Table 17 - Total measured consumption of school

O energetskoj reviziji ...

Heating Audit Report #077
Vukovar - Danube valley area

Address	Total metered consumption kWh/a	Calculated consumption kWh/a	%	Metered
	701	701	-	701
079-YUD-0XPS_School	193	27.1%	190.0	
079-YUD-0XPS_Danube valley area	25	3.5%	22.1	
079-YUD-0XPS_Danube valley area	52	4.4%	51.1	
079-YUD-0XPS_Heat plant building	13	2.0%	14.0	
080-YUD-0XPS_Household 10	30	0.2%	49.5	
081-YUD-0XPS_Household 11	47	0.2%	44.8	
082-YUD-0XPS_Household 12+heat+cool office	40	3.4%	39.5	
083-YUD-0XPS_Household 13+heat+cool office	20	3.2%	20.2	
40x audited YUD-0XPS_Heat plant 14	3	1.0%	7.7	
40x audited YUD-0XPS_Cycles	145	19.2%	153.5	
40x audited YUD-0XPS_Cycles	20	2.8%	19.2	
40x audited YUD-0XPS_Cycles	24	12.8%	20.1	
40x audited YUD-0XPS_School 15	5	0.4%	5.1	
40x audited YUD-0XPS_House 16	3	1.0%	7.7	
40x audited YUD-0XPS_office	20	2.7%	19.2	
TOTAL	791	100.0%	701	

Table 18 – Baseline metered consumption of heating

Year	Consumption kWh/a	Consumption kWh/a	Price per kWh/a	Cost kWh/a	% total metered
2012	62,436.6	609.0	1.20	74,922.9	19.2%
2013	48,494.7	320.0	1.20	57,328.2	19.2%
2014	31,442.3	540.0	1.20	57,752.0	19.2%
Average	47,376.5	521.1	1.20	59,861.2	

Table 19 – Summary of diesel consumption

Year	Consumption kWh/a	Consumption kWh/a	Price per kWh/a	Cost kWh/a	% total metered
2012	20,352.5	20.9	0.11	2,293.8	5.1%
2013	22,452.3	22.6	0.11	2,491.5	5.1%
2014	22,952.5	22.7	0.11	2,496.3	5.1%
Average	22,005.2	22.1	0.11	2,427.2	

Table 20 – Summary of annual energy consumption

As it can be seen in tables above, diesel consumption has a falling trend from 2012 to year 2014. The reason behind this is of financial nature, since there was an imposed budget cut in 2012 and ongoing, leading to imposed savings in fuel by turning off the heating plant for several hours a day.

It was noted by the facility management and occupants that a standard level of comfort was not always achieved during the heating season.

Since the building is heated with central heating it was necessary to verify the heating energy demand obtained with calculation, therefore the following methodology was applied:

- metered diesel consumption is recalculated to kWh

Heating Audit Report #077
Vukovar - Danube valley area

07/2/2013

In the table below the column "Baseline - METERED" shows the situation with the reported heating system consumption. The next column shows the situation when heating system losses were taken into account, but this case is treated in detail in the Heating Plant report.

	Baseline - METERED kWh/a	Baseline - Calculated (with boiler losses) kWh/a
Diesel	521,141.9	625,289.0
TOTAL	521,141.9	625,289.0

Table 21 – Baseline heating consumption (metered)

6.2. CALCULATED ENERGY CONSUMPTION - BASELINE

6.2.1. Energy Consumption for Heating

The heating calculation was based on EN ISO 13790 where the building heating consumption was calculated by taking into account physical properties (dimensions and areas) of windows, doors, walls, roof and floors. The calculation is based on heating degree days. Apart from that the calculation includes infiltration losses and solar and internal gains. The final energy demand figure is obtained when building heating demand is increased by heating system losses. A detailed calculation is presented in Annex 2. In addition to the baseline scenario, the recommended envelope efficiency measures are presented in the following chapters, showing a significant decrease in annual heat demand. The calculation of energy used for heating according to EN 13790 takes into account boiler losses and distribution system losses. The energy consumption for heating according to EN 13790 takes into consideration only one heating source – central heating system.

The total calculated heating energy demand of the building amounts to 625MWh/a, while the metered energy demand amounts to 521MWh/a.




Figure 15 – Comparison of reported and calculated heating energy consumption

O energetskoj reviziji ...

Report No. 077
Version 1 - Draft version

Page 52
07/2/2013

The calculated baseline is approximately 104 MWh/a higher than the reported baseline value. As discussed above, the heating comfort inside the building is not always met.

6.2.2. Electrical Energy Consumption

The calculated electrical energy for the baseline scenario was consumed for lighting, cooling and office equipment as presented in Table 22. The calculation is derived from a count of all electrical devices in the building and an estimate of usage throughout the year.

Category	Lighting	Office equipment	Total
MWh/a	9,527.3	15,699.0	25,026.3
kWh/a	2.5	15.7	23.0

Table 22 – Calculated electrical energy usage

Report No. 077
Version 1 - Draft version

Page 52
07/2/2013

7. ENERGY EFFICIENCY MEASURES

7.1. BUILDING ENVELOPE

Table 23 summarizes the above renovation cases for the entire building envelope. The U-value is the U-value of each element multiplied by the area of each element, indicating how much heat is transferred per unit of temperature difference between the external and internal air. Implementing the above measures increases the envelope performance as measured by the total U-value by 63%.

	Baseline	Renovated	Improvement %			
	U [W/m ² K]	A [m ²] U [W/m ² K]	U [W/m ² K]			
Wall 1	1.059	1,320.1	0.329	1,480.1	490.0	90.61%
Windows 1	1.060	372.0	0.090	372.0	671.0	0.00%
Windows 2	1.500	67.0	0.051	67.0	94.0	66.00%
Door 1	1.060	75.5	0.060	75.5	45.0	0.00%
Roof	4.124	955.0	2,350.6	955.0	290.1	32.61%
Basement	1.075	955.0	1,007.6	955.0	1,007.6	0.00%
Total			9,325.4		3,471.6	62.61%

Table 23 – Envelope efficiency improvements

This increased envelope performance leads to savings in the heat load which is to be met by the heating plant. The heat load by element for the baseline and renovated envelope is presented in Table 24 and Table 25 is also site and specific per meter squared values respectively, showing a 62% decrease overall in the calculated heating load due to increased thermal performance and reduced infiltration.

	Envelope upgrade heat load	Envelope heat load	Savings	Savings
	cWh/a	cWh/a	cWh/a	%
Walls	109,672.2	21,270.6	88,401.6	81%
Windows/doors	45,289.4	85,906.1	9,313.3	21%
Roof	175,057.5	12,942.4	162,115.1	93%
Basement	49,348.9	49,348.9	0.0	0%
Infiltration	102,606.2	78,927.9	23,678.4	23%
Ventilation	0.0	0.0	0.0	0%
Internal gains	-8,746.2	-8,746.2	0.0	0%
Solar gains	-23,019.9	-18,960.2	-4,059.7	-18%
Total heat load	450,208.1	170,798.4	279,410.6	62%

Total savings [kWh/a] 279,448.6
% savings 62.1%

Table 24 – Absolute heating load envelope improvement

O energetskoj reviziji ...

Energy Audit Report #077
Building - Building info

07.2.2013

	Baseline	Envelope	Savings	Savings
	heating load	upgrade heating load	tWh/m ² /a	%
Walls	35.4	6.9	28.5	82%
Windows/doors	14.6	11.6	3.0	21%
Roof	56.5	4.2	52.3	93%
Basement	15.9	15.9	0.0	0%
Infiltration	33.1	25.5	7.6	23%
Ventilation	0.0	0.0	0.0	0%
Internal gains	-2.8	-2.8	0.0	0%
Solar gains	-7.4	-6.1	-1.3	-18%
Total heat load	145.3	55.1	90.2	62%

% savings: 62.1%

Table 25 – Specification load envelope improvement.

The final calculated heating load after implementation of energy efficiency measures amounts to 200 kWh (see Annex 2 for calculation details) and the annual energy demand due to building losses drops from 400 MWh/a to 171 MWh/a. The drop occurs due to envelope insulation and reduction in infiltration losses due to enhanced window properties. Envelope insulation will serve as the basis for other calculations where various other heating sources will be considered.

7.2. HEATING SYSTEM

According to the baseline, energy demand due to heating system losses amounts to approx. 173 MWh/a with 72% heating system efficiency (includes heating distribution and regulation system efficiencies).

The heating demand, by taking into account the envelope renovation case, would amount to 237 MWh/a. If the building stays connected to the central heating system and the internal distribution system is renovated the overall system efficiency would increase to 81%.

Financial parameters of each project are elaborated in section 8.

7.3. VENTILATION SYSTEM

No measures recommended.

7.4. COOLING SYSTEM

No measures recommended.

Energy Audit Report #077
Building - Building info

07.2.2013

7.5. LIGHTING SYSTEM

A lighting system efficiency project was created as follows:

- Replacement of T8 fixtures 2x36W with HE T5 2x18W
- Replacement of T8 fixtures 1x36W with HE T5 1x18W
- Replacement of T8 fixtures 2x36W with HE T5 2x28W
- Replacement of incandescent lamps with CFL

Lighting renovation proposed replacement of incandescent lamps as the major energy saving measure regarding electrical energy. See Table 29 – Project 2 costs specification for the detailed line items of this project.

Lighting

Baseline

Type	No.	Bulbs	Watts	Bulbs	Watts
13 Fluorescent 2x36W	4	2	36	13%	531.1
13 Fluorescent 1x36W	127	1	36	13%	3,725.5
13 Fluorescent 2x28W	11	2	28	13%	902.4
Incandescent 100W	25	1	100	0%	24,500.0
TOTAL	163		203		9,527.0

Lighting

Renovation

Type	No.	Bulbs	Watts	Bulbs	Watts
13 Fluorescent 2x36W	4	2	36	0%	237.4
13 Fluorescent 1x36W	127	2	14	0%	3,789.4
13 Fluorescent 2x28W	11	2	28	0%	635.0
CFL 28W	25	1	28	0%	635.0
TOTAL	163		96		3,222.8

Table 26 – Comparison of baseline consumption and renovated consumption

7.6. SANITARY HOT WATER

Building is already connected to a SHW solar thermal system which is working properly. The system consists of solar thermal panels and uses electricity as backup. The solar system is currently overheating when there is no SHW demand, therefore it is strongly recommended to change the system to a drain back system, however before installing the system it should be checked whether the collectors are allowed to be emptied. The drain back system automatically drains the solar medium into a special tank and does not heat up the SHW when not needed.

7.7. OTHER ELECTRICAL EQUIPMENT

Electrical equipment within the building is mostly administrative. This equipment is considered necessary for normal operation of the teaching process; therefore the only EE measure in this section is the replacement of the pumps with new VFD pumps.

O energetskoj reviziji ...

Fleet Audit Report 07						4/2007
Wheeler - Delray Beach						07/2/2003
Equipment		Exterior		Interior		
No.	Unit	Mark	Model/Year	No.	Unit	Model/Year
PC	1	J30	3/96/96	PC	J30	5/9/96
IV	1	J30	5/2/94	IV	J30	5/2/94
III	2	J30	4/20/94	III	J30	4/20/94
II	2	J30	4/20/94	II	J30	4/20/94
I	6	J30	4/20/94	I	J30	4/20/94
Total				Total		

Table 23-2 Other Selected Accounts

Hung Audi, Roskilde 077
Møllevang - Dronningens vej 4
DK-4600 Roskilde

ENERGY EFFICIENCY PROJECT

There are also non EE measures identified during inspection which have to be addressed prior to implementation of project. Some of the EE measures are described in chapter below.

8.1 PROJECT DESCRIPTIONS AND ACCOUNTING

EE Project 1 to sees envelope upgrade of wall, roof insulation and new windows. As presented in chapter 7.1, the U-values of respective building elements significantly reduced. The specific costs (k/m²) of each measure include materials and works. The total estimated costs are 100,325£.

Description of IC investment	Unit	Quantity	Unit price (EUR)	Subtotal (EUR)
Project 1 - Building envelope				
Walls insulation with EPS-foam and ventilation with linear gains, improvement of roof ventilation and PIR foam insulation new roof loss a planer and decreases the winter pressure. The materials included as follows: 1) a) due to the thermal characteristics of the house.	m ²	1,790.6	25.0	44,770
Replacement of old windows with new PVC ones (U=1.4) and 1) b) due to the ventilation system, insulation, thermal planning around windows, all as per plan for 2 years after delivery Annex 2	m ²	67.60	125.00	8,450
Replacement of a roof - insulate and fit lighting equipment of the starting - end. Works include thorough inspection, replacement of damaged membrane and fitting of new drainage.	m ²	110.00	30.00	3,300
Delivery of the following coverings: PIR foam insulation board, roof insulation board, thermal mats, thermal mats, insulation of the floor of the lower part of the building, and panels, roof covering and sheeting has to be installed, garments and ad.	m ²	965.75	45.00	43,400

Table 20 - Prevalence of various forms of

EE Project 2 includes replacement of lamps as presented in chapter 7.5. The total number of lamps which are recommended to be replaced is multiplied with a price which includes the cost of the lamp and installation cost in order to obtain the total cost of the proposed project. The cost for new lighting includes labor costs of uninstallation and disposal of old fixtures and bulbs.

Description and Item	Unit	Quantity	Unit Price EUR	Total EUR
EC project 2 Electrical system				
1 CT 20W	pcu	20	10,00	200,00
2 Fluxgate Hc2-20W	pcu	15	40,00	600,00
3 Fluxgate Hc2-14W	pcu	120	40,00	5,000,00
TOTAL PROJECT 2				5,600,00

Tabel 29 - Preços 2009/2010

O energetskoj reviziji ...

Hesgj-Audi, Raco s. D77
Vukovar - Osječko-Baranjska
07.12.2013

EE Project 3: The additional cost in this case is the refurbishment of the existing substation distribution system, installation of TRVs on the radiators, as well as replacement of the existing pumps with new ones with VFD. The total costs are approx. 13.200 €.

#	Description of EE measure	Unit	Quantity	Unit price [EUR]	Subtotal [EUR]
EE Project 3: Additional costs for energy efficiency measures					
1	Replacing additional thermal insulation (radiators (polyurethane insulation) and TRV valve)) on one radiator	pc	1	134,0	134,0
2	Replacing additional thermal insulation (radiators (polyurethane insulation) and TRV valve)) on one radiator	pc	1	1.000,0	1.000,0
3	Replacing the existing pump with a variable speed pump (VFD)	pc	1	2,0	2,000,0
4	Cruciform gear pump + gear material heating network	pc	1	2.000,0	2.000,0
TOTAL PROJECT 3					13.200,0

Table 30 – Project 3 cost specification

8.2. NO-EE MEASURES

A monitoring system is recommended for proper accounting of energy consumption and to provide a baseline for future EE measures.

#	Description of no-EE measure	Unit	Quantity	Unit price [EUR]	Subtotal [EUR]
Monitoring					
1	Energy Monitoring software, data logger software, training	pc	1,0	12.000,0	12.000,0
TOTAL MONITORING					12.000,0

Table 31 – Monitoring cost specification

Further measures include the internal painting, installing drain back equipment, check and fixing possible deficiencies in the solar thermal system.

#	Description of no-EE measure	Unit	Quantity	Unit price [EUR]	Subtotal [EUR]
No-EE measures					
1	Internal painting of radiators	pc	1,0	3.200,0	3.200,0
2	Installing drain back equipment and repairing solar thermal system	pc	1,0	3.000,0	3.000,0
3	Cruciform gear pump + gear material heating network	pc	1,0	2.000,0	2.000,0
TOTAL NO-EE MEASURES					8.200,0

Table 32 – Non-EE measures cost specification

8.3. FINANCIAL VIABILITY

Based on the costs and energysavings, a yearly cash flow analysis was performed. Fuel escalation was applied separately to baseline and proposed projects according to the fuel escalation rate of 2% per year. Table 33 presents an overview of the cash flow analysis, including the financial indicators net present value, internal rate of return, and the simple payback period.

Hesgj-Audi, Raco s. D77
Vukovar - Osječko-Baranjska
07.12.2013

	1. Envelope renovation	2. Lighting renovation	3. Heating system renovation *
Fuel savings [EUR/a]	35.288,9	0,0	2.386,6
Electricity savings [EUR/a]	0,0	484,1	42,1
Hot water cost savings [EUR/a]	0,0	0,0	0,0
Total investment cost [EUR]	-100.225,7	-5.310,0	-13.870,0
NPV [EUR]	250.278,6	-2.638,6	10.346,0
Project life [Years]	20,0	10,0	20,0
IRR [%]	37,8%	-1,5%	19,1%
Simple payback [Years]	2,38	12,21	5,68

Table 33 – Financial summary *

8.3.1. Energy Saving Potential

The table and figure below compare the reported and baseline energy consumption in kWh with the different scenarios of energy efficiency projects.

	Baseline scenario	1. Envelope renovation	2. Lighting renovation	3. Heating system renovation
Heat consumption				
Heating cost savings [kWh/a]	625.200,0	257.163,9	21.021,1	
Baseline consumption [kWh/a/m²]	201,9	79,9	8,9	
Heating savings [kWh/a]	625,2	177,2	11,9	
Secondary consumption				
Heating cost savings [kWh/a]	25.028,9	10.028,9	1.028,9	2.2.873,9
Baseline consumption [kWh/a/m²]	7,4	7,4	0,1	7,5
Heating load savings [kWh/a]	25,0	10,0	1,0	2,2
Total savings [kWh/a]	388.123,1	167.200,8	16.023,8	16.023,8
Total savings [%]	9,0%	14,2%	1,0%	1,0%

Table 34 – Comparison of energy efficiency projects, baseline and reported energy consumption*

* The heating 4% and 10% cost reduction is calculated as the new baseline for energy savings calculation

** The heating 4% and 10% cost reduction is calculated as the new baseline for energy savings calculation

O energetskoj reviziji ...




Figure 16 – Comparison of energy efficiency projects, baseline and reported energy consumption



8.4. RECOMMENDATIONS

8.4.1. EE-Project Summary

From the financial results in Table 33, a summary for each EE project can be drawn based on their highest NPV.

Project	NPV	Investment cost	IRR	Simple PB
1. Envelope renovation	280,279	100,226	37,8%	2,8%
3. Heating system renovation *	10,346	13,870	19,1%	5,6%
2. Lighting renovation	-2,653	5,800	-1,5%	12,2%

Table 33 – Ranking based on highest NPV

In the above Table 33, the envelope project is considered a stand-alone project. The envelope upgrade is a precondition before any heating system upgrades. Therefore, the heating projects (Heating system renovation) are disaggregated as incremental to the envelope. The heating NPV and IRR consider the envelope as the new baseline for energy savings calculations. Heating system upgrade projects are then ranked as to their highest NPV.

8.4.2. Final Recommendations

Table 36 below summarizes the final package of energy efficiency measures and related general building improvements. The most economically feasible projects are selected based on the financial cutoff rate of return, 10%.

The baseline for comparison is the actual construction condition of the buildings and technical systems. The economic feasibility of each identified measure was evaluated based on the estimates of construction and installation. Operational energy savings were calculated using standard calculation methods for heating and electricity demand, and are compared to the baseline conditions.

Project	Building		Carbon Savings tCO ₂ /a	Cash Savings €/a	Investment cost €	Simple payback Year
	Heating Savings MWh/a	Electricity Savings MWh/a				
1. Envelope renovation	300,123	0	0	35,284	100,226	2,8%
2. Heating system renovation *	26,257	0	0	2,206	13,870	5,6%
3. Lighting renovation	0	0	0	0	5,800	12,2%
4. Renovation of windows	0	0	0	0	12,000	10,0%
Total	434,382	0	0	37,690	126,096	3,35
Non-EU measures	0	0	0	0	0	0
Total savings of the building	434,382	0	0	37,690	126,096	3,35
Initial costs of the building	0	0	0	0	0	0
Building Share, heating system or heating coil thermal system	0	0	0	0	0	0
Building area approach total thermal value heating savings per m ² (without non EU measures)	0	0	0	0	0	0
Replacement of heating system	0	0	0	0	0	0

Table 36 – Recommended measures

O energetskoj reviziji ...

Report Date: 07/07/2013
Report Delivery No.: 1

9. BUILDING CHARACTERISTICS WITH REGARD TO HAZARDOUS MATERIALS

9.1. OVERVIEW

Type of Use (Office, Educational, Hospital, etc.)	Office
Year of construction:	1930
Year of significant reconstruction/reinforcing work:	Windows 2000
Partitioning of building:	1 floor + g
Type of Roof:	Asbestos roof

Table 37 – Building properties

Evidence	Yes	No	Comments	Likely
Construction materials used (e.g., steam radiator, heating boiler, oil tank etc.)	Y			ACM
Construction materials / insulation system	Y			ACM
Insulation panels	Y			ACM
Roof/ceiling/thermal insulation	Y			ACM
Roof/ceiling/thermal insulation Sheets	Y			ACM
Velour / PVC (bearing with asbestos ACM glue factor)	Y			ACM
High storage shelves / Asbestos shelves	Y			ACM
Decorations (e.g., asbestos containing asbestos) (e.g., vinyl, radiology / X-ray)	Y			ACM
Decorative	Y			ACM
Construction materials / Heavy Saving Bulbs recycling	Y		Indirect usage decreases	Mercury

Table 38 – Likelihood of hazardous material existence (based on interview)

Report Date: 07/07/2013
Report Delivery No.: 1

9.2. SUMMARY OF HAZARDOUS MATERIAL SURVEY

9.2.1. Suspect Hazardous Material

During the survey, the following products have been identified to be potentially a hazardous material

#	Group	Suspect Product	Purpose	Location	Analysis Result	Amount (m ²)
1	Asbestos	Sheet	Roof	Roof	Visual inspection - ACM detected	233,3 m ²
2	Other	Sheet or insulated sheet	out of use / early work	Roof building	-	137

Table 39 – Identified Hazardous Materials overview (in bold: evidenced material)

The results of the visual and laboratory analysis are summarized in the following section.

9.2.2. Classification of Risk and Abatement Urgency

The subject building has got as indicated with Y:

- Y Strongly bound asbestos containing materials : Asbestos containing fiber cement panels (incl. "Solenit") and/or other strongly bound asbestos products such as flange sealings
- N Night storage heater
- N Flexible asbestos containing products (strings, mattresses)
- N Friable asbestos products
- N Deposits of lead-based paints
- Y Spent Compact Fluorescent lamps

9.2.3. Identified Hazardous Material #1: Fiber Cement Panels

According to the Urgency Checklist (see Annex 2), the identified deposits of hazardous materials are deemed to be of small risk and require professional statement not urgently (within 3 years).

9.2.4. Identified Hazardous Material #2: Spent Compact Fluorescent Lamps

According to the Standard Operation Procedure for the Collection and Recycling of Compact Fluorescent Lamps, which have to be generally considered to contain Mercury, the identified deposits of hazardous material are deemed to be of an issue that requires a territorial awareness raising campaign and the introduction of an incentive system for CFL recycling.

*Overall weight is calculated from the quantity whereas no unit (kg/m²)
**urgently (within 3 years), urgently (within 2 years), immediately (within 0,5 years) according to criteria of the urgency table of Annex 2

O energetskoj reviziji ...

Ho geplaat: Aanvraag ID:
Waarde: - Datum van vraag:

Code:
07/12/2013

9.3. PROPOSED HAZARD MANAGEMENT

Referring to the environmental laws and regulations of the Kosovo, the appropriate EU directives and the World Bank requirements, the following mitigation measures are proposed in the course of EE measures are to be foreseen:

9.3.1. Proposed Hazard Management – Asbestos-Fiber Cement Panels

The general approach while handling this material is that contractors avoid crushing/damaging of asbestos plates from the roof and/or from the wall insulation and deposit them in an organized manner on the construction sites.

9.3.1.1. Maintenance

Prohibit any mechanical stress on fiber-cement panels (no drilling, cutting, smashing, cutting, dropping etc.)

9.3.1.2. Removal

Amount:	9 358 m ²
Location:	Roof

The Removal of ACM containing Fiber-Cement Panels ('Eternit' / 'Salonit' or other) belongs to the removal of so called strong bonded ACM, due to the fact that those panels consist of a lesser amount of asbestos, which is firmly embedded in a cement matrix.

However, whenever the cement panels are mechanically damaged or destroyed, ACM dust is set free.

Best practice is to prevent or minimize dust release, resulting from a destruction free removal process.

Main Remediation WorkSteps

- Prohibit any mechanical stress on fiber-cement panels (no drilling, cutting, smashing, cutting, dropping etc.)
- Strike unmounting procedure using lifting devices
- Wear appropriate respiratory protection FFP3 and disposable coveralls
- Remove panels before uninstall;
- Collect panels without destruction
- Pack them plastic foil / e.g. panel big bags with Asbestos Label
- Only store in an interim storage until transport and disposal at appropriate disposal site.

Further hints are:

- Nails/rivets shall be removed with sharp tools
- If the fixing can't be released, small sheets can be pried out one by one
- Demounting of asbestos cement panels shall happen in a work back way, for roofs from the ridge to the eaves, for walls from top to bottom

Ho geplaat: Aanvraag ID:
Waarde: - Datum van vraag:

Code:
07/12/2013

- When removing fixation materials, the product has to be secured against sliding off
- Wherever possible, products shall be lifted off rather than carried out
- Encrustation or plant cover can be scraped off, using a wood scraper
- Broken bits and debris shall be wrapped in dust proof foil or bag
- The contaminated material has to be transported to the ground carefully
- The transportation of asbestos cement products has to take place in a way, that prevents asbestos dusts to be released (packing)
- For cleaning use: Heless vacuum cleaners is only.
- Storage and transport of material has to happen in sealed, closed containers

To be avoided:

- Breaking, cutting, throwing and milling off sheets
- Drilling, sawing, grinding with fast running machinery
- Cleaning with high pressure cleaners
- Shaking out of carcasses or under coversheeting
- Usage of debris chutes

9.3.1.3. Supervision of Asbestos Abatement

Specifically due to the risk that abatement was performed contrary to above mentioned regulations, it is highly recommended that the mitigation works are to be guided by a specifically trained (certified) independent expert (e.g. chartered civil engineer with asbestos abatement knowledge).

9.3.1.4. Asbestos Transport and Disposal

The Ministry of Environment and Spatial Planning (MESP) is working towards the establishment of an (interim) storage facility for hazardous material.

Contractors should liaise with MESP regarding final disposal and treatment options, licensing requirements and applicable local regulations on this issue.

The contractor has to prepare and to provide a coordinated transport and disposal concept as soon as the contract is signed. This concept has to include, based on the appointment with the MESP, a signed confirmation of the nearest suitable approved landfill to accept construction wastes.

The Contractor shall perform or carry out all transports in fully accordance with the International Statutory and Technical Rules (ADR) and/or corresponding national rules. According to this, the transport containers and equipment require certain danger marks depending on shipped masses. Vehicles and their drivers require specific ADR approval or an ADR license. Each driver has to carry documents identifying origin and destination, mass and waste type of his way.

The contractor has to prepare and to provide a coordinated transport and disposal concept as soon as the contract is signed. This concept has to include a signed confirmation of the subcontracted transhipping to be carried required licenses.

Removed ACM shall be packed in double polythet at least 0.2 mm thickness and stored in Big-Packs clearly visibly signed with the Asbestos logo. Whenever transported with fork lifters, Big-Packs have to be set on wooden euro pallet in order not to damage the big-packs by the forks.

O energetskoj reviziji ...

Hrgj-Audi-Renew-BII
Vetvni - Detaljnija rev.

čas
07.12.2013

9.3.2. Proposed Hazard Management – Lead-Based Paint

There is no evidence of the presence of lead-based paint.

9.3.3. Proposed Hazard Management – CFLs

9.3.3.1. Maintenance

Prohibit any mechanical stress on compact fluorescent lamps (no smashing, dropping etc.)

In case lamps are broken, follow the typical instructions¹

Before Clean up

- Have people and pets leave the room.
- Air out the room for 5-10 minutes by opening a window or door to the outdoor environment.
- Shut off the central forced air heating/air-conditioning system, if you have one.
- Collect materials needed to clean up broken bulb:
 - a stiff paper or card board;
 - a sticky tape;
 - a damp paper towel or disposable wetwipes (for hard surfaces); and
 - a glass jar with a metal lid or a sealable plastic bag.

During Clean up

- Do not use the vacuum cleaner! Vacuuming is not recommended unless broken glass remains after all other cleanup steps have been taken. Vacuuming could spread mercury-containing powder or mercury vapor.
- Be thorough in collecting broken glass and visible powder. Scoop up glass fragments and powder using stiff paper or card board. Use sticky tape, such as duct tape, to pick up any remaining small glass fragments and powder. Place the used tape in the glass jar or plastic bag. See the detailed cleanup instructions for more information, and for differences in cleaning up hard surfaces versus carpeting or rug.
- Place cleanup materials in sealable container.

After Clean up

- Promptly place all bulb debris and cleanup materials, including vacuum cleaner bags, outdoors in a trash container or protected area until materials can be disposed of. Avoid leaving any bulb fragments or cleanup materials indoors.
- Next, check with your local government about disposal requirements in your area, because some localities require fluorescent bulbs (broken or unbroken) be taken to a local recycling center. If there is no such requirement in your area, you can dispose of the materials with your household trash.
- If practical, continue to air out the room where the bulb was broken and leave the heating/air conditioning system shut off for several hours.

¹ e.g. Instructions of the U.S. Environmental Protection Agency, <http://www2.epa.gov/cfl/clean-up.html>

Hrgj-Audi-Renew-BII
Vetvni - Detaljnija rev.

čas
07.12.2013

9.3.3.2. Recycling of spent CFLs

In Kosovo, spent CFLs, whereas all of them are containing small portions of Mercury and other hazardous materials emittable to atmosphere, water or soil, are currently neither separately collected, nor properly recycled or treated.

Thus, spent CFLs are mainly disposed on regional sanitary landfills in Kosovo.

Recently, the only possibility to treat such lamps properly, i.e. to separate Mercury and other gases from glass and scrap metal, is its export to foreign countries, where authorized companies are maintain CFL recycling centers (e.g. Alba-SRB).

For the collection and management, spent CFLs have to be stored in certain grid shaped cardboard containers on Euro pallets and wrapped with stretch foil, while energy safety bulb (likely to be found during EE implementation work) have to be stored in sealable open-top UN bins (pooler).

Method example Alba-SRB²:

Intersohrt, an ALBA Group company, provides a convenient service aimed at saving consumers a trip to the local recycling plant: the Intersohrt collection box is designed especially for taking back illuminants in small and medium quantities. Retailers and managed areas set up these inexpensive boxes in their sales and storage areas, allowing end users to dispose of used illuminants in-store when purchasing new ones. In addition to the collection of old bulbs and other lamps, the service also covers their recycling and documentation.

Collection boxes are available for different types of illuminants. Once a box is full, a quick phone call is all that is needed to arrange for it to be picked up. The entire take-back and disposal process is handled by Intersohrt, in close collaboration with service partners throughout Germany.

In the future, the residual mercury-containing phosphor powder (1-3 % of CFL weight, rest is recyclable glass and metal scrap) is due to lack of economic methods at least for partially disposed as hazardous waste on suitable landfills. In the usual process the gaseous portion goes into the atmosphere.

9.4. COST ESTIMATE FOR ABATEMENT AND DISPOSAL OF SELECTED HAZARDOUS MATERIAL

Costs for the removal of hazardous material apply in case that the implementation of energy efficiency measures requires the abatement of hazardous material.

Asbestos containing material (ACM)

Based on similar ACM projects the following specific work amount has been estimated:

- Total amount approx. 9.552 m² of asbestos cement roof
- Estimated Weight (17 kg/m²): approx. 16.248.6 kg
- Product: Asbestos Cement (Salonit)

² <http://www.alba-deutschland.de/recycling/katastrophale-waste/>, <http://www.alba-deutschland.de/recycling/>


O energetskoj reviziji ...

Utvrđene EE mere


- › Renoviranje zidova
- › Renoviranje krova
- › Zamena prozora i vrata
- › Zamena goriva
- › Poboljšanje sistema grejanja
- › Popravka rasvete
- › Solarno grejanje

- › Sve brojke su prikazane u procentima:
 - › Broj objekata u kojima su primenjene mere je podeljen sa ukupnim brojem objekata


Utvrđene EE mere - renoviranje zidova




Utvrđene EE mere - renoviranje krova




Utvrđene EE mere - renoviranje prozora




Utvrđene EE mere - zamena goriva




Utvrđene EE mere - sistem grejanja




Utvrđene EE mere - sistem rasvete




Utvrđene EE mere - solarno grejanje




Sumirani rezultati - prosečna grejna površina objekta




Sumirani rezultati - prosečna godina gradnje




Sumirani rezultati - prosečne U-vrednosti pre




Sumirani rezultati - prosečne U-vrednosti posle




Sumirani rezultati - prosečna potrošnja grejanja pre




Sumirani rezultati - prosečna potrošnja grejanja posle




Sumirani rezultati - prosečna ušteda energije



Sumirani rezultati - prosečna ušteda energije %



Sumirani rezultati - prosečno spec. EE ulaganje



Profil



z.bacelic@ic-group.org

Zlatko BAČELIĆ MEDIĆ

- Iskustvo u upravljanju timom i koordinaciji projektima energetske efikasnosti, obnovljivim energijama i primeni novih tehnologija
- Vođa tima za energetske revizije u javnom, privatnom i industrijskim sektoru
- Iskusto u obuci kadrova u zemljama u razvoju
- Izuzetno iskustvo u tehničkom oblikovanju i pripremi finansijskih analiza energetske efikasnosti i u projektima primene obnovljive energije
- Stručnost u optimizaciji i optimizovanju troškova u projektima energetske efikasnosti
- Stručnost u analizi i proceni energetskih sektora, uključujući energetsko planiranje
- Projektno iskustvo širom Jugoistočne Evrope

Visit us on the internet ...

www.ic-ces.at

**We are looking forward
to the future.
Wherever!
Whenever!
With you.**



CES clean energy solutions GmbH
Schönbrunner Str. 297
1120 Vienna, Austria
T +43 1 521 69 – 0
www.ic-ces.at; office@ic-ces.at
UID: ATU 64715133, FN 320442p